

RAY-TECH INFRARED CORP.

TOTAL MAINTENANCE VEHICLE (TMV) / OPTIONS

OPTIONS

- A. Time Delay System (TDS)
Allows you to pre-set the time that the reclaimer will automatically turn on. (Set On Friday afternoon to turn on Sunday afternoon to be ready for Monday morning).
- B. Tool Storage Tray
(approx. 24" x 84" x 12"). Suspended under rear or side of truck.
- C. 24 Volt, 95 Amp Alternator
Modification of Vehicle battery system to provide a 24 volt circuit, and to replace The TMV standard battery/charger system.
- D. Folding Chamber
13' x 6' folding chamber with (4) independent operating systems. (2) 4' wide Systems on center chamber and (2) 2 ½' wide systems on each side folding Chamber. This will allow independent heating widths of 2½', 4', 6½', 8', 10½', and 13' x 6' long. Also included will be (1) additional 100 gal propane cylinder.
- E. 12 Volt Lighting
Two (2) multi-directional floodlights.
- F. Trailer Hitch
Reese Style (or equiv.).
- G. Aluminum Wind Guards set of 4
12" x 4' x 2" thick insulated Wind Guards – also protects concrete, grass, Building and other uses.
- H. Installation
Installation of unit on truck.
- I. Arrow Stik—47"L x 2 ¾" H x 4 3/8" D
With in-cab control module with a rotary switch and LED lights that show the flash pattern being used.
- J. Water Tank-----35 gallon PCO tank
35" L x 16" W x 21" H mounted on raised platform
- L. Hydraulically Operated Chamber Lift--in place of standard 24V electric winch

Additional charges may apply for installation of some options.